

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-20611-00-00

LEASE NAME Landwehr

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 7 TWP. 33 RGE. 10 ~~W~~ (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 7-15-92

Plugging Completed 2:30 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR B-Y Operating, Inc.

ADDRESS 251 N. Water, Suite 12, Wichita, Ks 67202

PHONE# (316) 263-7049 OPERATORS LICENSE NO. 30705

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-15-92 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation Depth to Top 4646 Bottom 4676 T.O. 4695

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	260	0
				4 1/2	4694	3493

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each:
Bottom Plug: Pumped 40 sx Common w/3% CC & displaced to 4300 ft.

Top plug: Pumped 300 lb H, 10 sx Gel, 50 sx Cement, 10 sx gel, 100 lb Hulls, 100 sx 60/40 w/6% gel. Had max pressure of 500 lbs & shut in pressure of 100 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: B-Y Operating, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Gary G. Burke (Employee of Operator B-Y Operating, Inc.)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 16 day of July, 19 92



Anna K. Burke
Notary Public

My Commission Expires: 4-30-96

RECEIVED
STATE CORPORATION COMMISSION
07-17-1992
JUL 17 1992
Wichita, Kansas