

15-007-20222-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

BARBER County. Sec. 5 Twp. 33 Rge. (E) 10 (W)

Location as "NE/CNWxSWx" or footage from lines W/2 W/2 NE/4
Lease Owner BEACON RESOURCES, CORP.
Lease Name TRAFFAS Well No. #1
Office Address 1000 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 1/12 19 73
Application for plugging filed 1/12 19 73
Application for plugging approved 1/12 19 73
Plugging commenced 1/12 19 73
Plugging completed 1/12 19 73
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well RUSS RIBERSTINE
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4643 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface loay, red rock		0	285	8 5/8	285	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st
plug @ 275 w/40 sks.
2nd plug @ 40' w/15 sks
Bridge RT w/ 35 sx
complete @ 1:30 AM 1/12/73

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1973

CONSERVATION DIVISION
Wichita, Kansas

04-12-1973


(If additional description is necessary, use BACK of this sheet).
Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GABBERT-JONES, INC. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as log and that the same are true and correct. So help me God.

(Signature) Jack W. Gabbert

Jack W. Gabbert
830 Sutton Place, Wichita, Kansas

Subscribed and sworn to before me this 11 day of April, 19 73



Marjorie Hall
Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

15-007-20222-00-00

TRAFFAS #1
 W/2 W/2 NE/4
 Section 5-33S-10W
 Barber County, Kansas

Commenced: December 26, 1972
 Completed: January 12, 1973

OPERATOR: BEACON RESOURCES CORP.

Depth From	Depth To	Formation	Remarks
0	15	Surface clay	Ran 7 joints of new 20# 8 5/8" casing set @ 285' w/175 sks common, 2% Gel, 3% EC P.C. 5:15 AM 12/27/1972 Cement Circ.
15	286	Red rock	
286	375	Shale	
375	500	Shale-Shells	
500	1275	Shale	
1275	1480	Shale-shells	
1480	1893	Shale-lime	
1893	2575	Lime-shale	
2575	2750	Lime	
2750	3759	Lime-shale	
3759	3865	Sand-lime	DRY AND ABANDONED
3865	3954	Lime-shale	
3954	4643	Lime	
4643	TD		

RECEIVED
 STATE CORPORATION COMMISSION
 APR 12 1973
 CONSERVATION DIVISION
 Wichita, Kansas

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the W/2 W/2 NE/4, Section 5-33S-10W, Barber County, Kansas, to the best of my knowledge and belief.

James S. Sutton, II
 James S. Sutton, II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 16th day of January, 1972, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
 Marjorie Hall, Notary Public

My commission expires
 November 29, 1975