

15-007-00723-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barber County, Sec. 16 Twp. 33S Rge. 10 (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW/4 SW/4

Lease Owner Toto Gas Company

Lease Name McReynolds Well No. 1

Office Address 5101 N. Pennsylvania, Oklahoma City 12, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Completed as oil well.

Date well completed June 16, 1961.

Application for plugging filed November 7, 1961.

Application for plugging approved November 16, 1961.


Plugging commenced November 24, 1961.

Plugging completed November 26, 1961.

Reason for abandonment of well or producing formation Declining oil production & increasing water production makes operation of well unprofitable and impractical.

If a producing well is abandoned, date of last production November 8, 1961.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Fred Hampel, Pretty Prarie, Kansas

Producing formation Mississippi Lime Depth to top 4546 Bottom 4566 Total Depth of Well 4950 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	SW w/show oil	3906	3918	8 5/8"	300'	None
Mississippi Lime	Oil and SW	4546	4566	4 1/2"	4627'	3485'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

5 sacks cement plug. Displaced with mud 3875 to 3890
Shot 4 1/2" casing off at 3485
500# Rock Bridge at 303
20 sacks cement plug 240 to 303
10 sacks cement plug Surface to 30

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1961
CONSERVATION DIVISION
Wichita, Kansas

11-29-1961

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Toland & Reeves, Kansas Permit No. 246


Address 1317 S. E. 29th St. Oklahoma City, Oklahoma

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
H. R. Thomson (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Thomson

SUBSCRIBED AND SWORN TO before me this 27th day of November, 1961.

(Address) Merilee A. Adams
 My commission expires 12-10-61.
 Notary Public.



12-005-00198-00-09

State of Kansas, Barber Co., SS
This instrument was filed for record on
the 27 day of 5th mo
A.D. 1961 at 1 o'clock P.M., and
duly recorded in book 20 on page 403

Register of Deeds

Fees

11-98-1691

DRILLERS LOG
McReynolds No. 1

15-007-00723-00-00

CASING RECORD: COMPANY: Arvel C. Smith DESCRIPTION: C NW 3E
 8 5/8" @ 300' CONTRACTOR: Red Tiger Drilling Co. 16-335-10W
 w/175 ex cement Barber County
 Kansas
 COMMENCED: May 11, 1961 ELEVATION: 1511 OF
 4627.14' of 4 1/2" cemented w/300 ex. COMPLETED: May 29, 1961 1514 RB
 TOTAL DEPTH: 4950

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed Shale	0	40	
Red Bed Shale	40	1040	
Shale	1040	1240	
Lime	1240	1283	
Shale	1283	1285	
Lime & Shale	1285	3505	
Sandy Lime & Shale	3505	3595	
Shale Lime	3595	3600	
Lime Shale	3600	3903	
Lansing Lime	3903	3960	
Lime Shale	3960	4122	
Lime	4122	4135	
Lime & Shale	4135	4200	
Lime	4200	4335	
Lime & Shale	4335	4479	
Lime	4479	4540	
Lime & Shale	4540	4546	
Mississippi	4546	4573	
Cherty Lime	4573	4632	
Shale	4632	4604	
Shale Cherty Lime	4604	4634	
Cherty Lime	4634	4725	
Lime Shale	4725	4864	
Lime	4864	4900	
Chalky Lime & Shale	4900	4903	
Viola	4903	4925	
Lime	4925	4950	

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1961
CONFIRMATION DIVISION
Topeka, Kansas

11-29-1961

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 1st day of June, 1961.

Mauro Head
Notary Public

My Commission Expires:

11-17-62