


15-007-20647-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 12 Twp. 33 Rge. 10 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
1980 FSL 660 FEL SE/4
Lease Owner Cities Service Oil Co.
Lease Name Grossick #1 Well No.
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/11/79 19
Plugging completed 9/14/79 19
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation Depth to top Bottom Total Depth of Well 4985
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	301	none
				5 1/2"	4984	3327'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 4828 to 4725' and ran 5 sacks cement. Shot pipe at 3320', pulled 79 joints. Squeezed hole with 8 sacks hulls, 25 sacks gel, mud from 4685 to 420', released plug and displaced with 125 sacks 50-50 pozmix, 4% gel and 3% cc. Cement from 420 to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
09-20-1979
SEP 20 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KESLO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of Sept., 19 79

Margaret Melcher
Notary Public.

My commission expires



KANSAS DRILLERS LOG

COMPANY Cities Service Company

SEC. 12 T. 33S R. 10W
LOC. C- NE SE

FARM Grossich "A" NO. 1

COUNTY Barber

ROTARY TOTAL DEPTH 4,985'
COMM. August 4, 1978
CONTRACTOR H-30, Inc.
ISSUED August 24, 1978

COMP. August 19, 1978

CASINO

10 3/4"
8 5/8" Set at 293' cemented w/200sxs cement
5 1/2" Set at 4,984' cemented w/300sxs cement
4 1/2"

ELEVATION 1,314 K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Sand	45'
Red Bed and Shale	810'
Lime and Shale	4,789'
Sand and Lime	4,810'
Lime and Shale	4,925'
Shale and Lime	4,985'
Rotary Total Depth	4,985'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1979
06-22-1979
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 24th day of
August, 1978.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982