


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Harper County, Sec. 9 Twp 31S Rge. 5W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW  
Lease Owner T. L. FERRIER  
Lease Name Schrock Well No. 1  
Office Address 200 West Douglas, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 9-24 1970  
Application for plugging filed 9-24 1970  
Application for plugging approved 9-24 1970  
Plugging commenced 9-24 1970  
Plugging completed 9-24 1970  
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4593 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	201'	8-5/8"	201'	Left in

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fluid to 175, 1/2 sx hulls, plug, 25 sx cement;  
Fluid to 40', 1/2 sx hulls, plug, 10 sx cement;  
Two sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.  
Address 737 First National Bank Bldg., Wichita, Kansas 67202


STATE OF KANSAS COUNTY OF ss.  
James L. Donelson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson

737 First Nat'l Bk Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of September, 1970



Ella Priess

Notary Public.

DRILLERS' LOG

T. L. FERRIER  
 Schrock No. 1  
 SW SW NW, Sec. 9-31S-5W  
 Harper County, Kansas

ELEVATION: 1326 K.B.

Commenced: 9-14-70  
 Completed: 9-24-70

SURFACE CASING: 201' of  
 8-5/8" cemented w/200 sx  
 cement, 3%cc. 9-15-70

FORMATION

DEPTH

Surface Hole	208
Shale	530
Shale & Lime	1317
Lime & Shale	1482
Shale & Lime	2384
Lime & Shale	2598
Shale & Lime	3232
Sand	3314
Shale	3388
Shale & Lime	3712
Lime & Shale	3830
Shale & Lime	4104
Lime	4186
Shale & Lime	4556
Sand	4593 T.D.

RECEIVED  
 STATE CORPORATION COMMISSION  
 9-30-70  
 SEP 30 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
 JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 29th day of September, 1970.

My Commission Expires:  
 August 25, 1972

*Ella Priess*  
 Ella Priess, Notary Public

