
15-135-00198-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ness County. Sec. 31 Twp. 20S Rge. 22 (E) X (W)

Location as "NE/CNW¼SW¼" or footage from lines SE SE NE

Lease Owner M. B. Armer

Lease Name Foos Well No. 1

Office Address 710 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-17 19 53

Application for plugging filed 5-17 19 53

Application for plugging approved 5-17 19 53

Plugging commenced 5-17 19 53

Plugging completed 5-17 19 53

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 4507 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	221	None
SEE ATTACHED LOG						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 220' with heavy mud, set plug and cemented with 20 sacks through drill pipe. Filled hole to 35', set plug and cemented to bottom of cellar with 10 sacks.

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1953
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Carl Todd Drilling Company

Address 404 KFH Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

L. P. Sonnenberg (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. P. Sonnenberg

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 1953

Lorraine M. Johnson
Notary Public.

My commission expires Oct 13, 1956

23-8390-s 6-51—20M

PLUGGING
FILE SEC 31 T 20 R 22W
BOOK PAGE 102 LINE 6

THE CARL TODD DRILLING COMPANY
404 KFH Building
Wichita, Kansas

15-135-00498-0000

M. B. ARMER
#1 Foos
SE SE NE 31-20S-22W
Ness County, Kansas

COMMENCED: May 1, 1953

COMPLETED: May 17, 1953

ELEVATION: 2215 DF

0	- 50	Surface clay and rock
50	- 100	Shale
100	- 221	Shale and shells
221	- 500	Shale and shells
500	- 600	Shale
600	- 815	Red bed and shale
815	- 835	Hard shells
835	- 915	Red bed and shale
915	- 1115	Sand
1115	- 1465	Red bed and shells
1465	- 1470	Anhydrite
1470	- 1495	Anhydrite
1495	- 1700	Red bed and shale
1700	- 1725	Red bed and shale
1725	- 1870	Salt and shale
1870	- 2025	Brown shale and lime
2025	- 2190	Shale and shells
2190	- 2240	Lime and shale
2240	- 2350	Lime and shale
2350	- 2465	Shale and lime
2465	- 2510	Lime and shale
2510	- 2595	Lime and shale
2595	- 2665	Shale and lime
2665	- 2725	Lime and shale
2725	- 2790	Lime and shale
2790	- 2890	Lime and shale
2890	- 2975	Lime and shale
2975	- 3045	Lime and shale
3045	- 3095	Shale and lime
3095	- 3165	Shale and lime
3165	- 3265	Lime and shale
3265	- 3323	Lime and shale
3323	- 3385	Lime and shale
3385	- 3430	Lime and shale
3430	- 3515	Lime
3515	- 3585	Lime
3585	- 3630	Lime
3630	- 3730	Lime
3730	- 3795	Lime
3795	- 3840	Lime
3840	- 3875	Lime
3875	- 3935	Lime
3935	- 3987	Lime
3987	- 4015	Lime
4015	- 4070	Lime and shale
4070	- 4110	Lime
4110	- 4137	Lime
4137	- 4173	Lime and shale
4173	- 4217	Lime and shale
4217	- 4256	Lime
4256	- 4286	Lime and shale
4286	- 4343	Lime and shale
4343	- 4389	Lime and shale
4389	- 4409	Chert and shale
4409	- 4460	Mississippi
4460	- 4497	Lime and chert
4497	- 4507	Lime and chert
4507		Rotary Total Depth

CASING RECORD

Set 8-5/8" @ 221', cemented with 150 sacks & 3 sacks CC

TOPS

Heebner	3742
Lansing	3790
Mississippi	4407

State of Kansas)
County of Sedgwick)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 20th day of May, 1953.

Notary Public

My commission expires Oct. 13, 1956

RECEIVED
STATE CORPORATION COMMISSION
MAY 2[illegible] 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 31 T 20 R 22W
BOOK PAGE 102 LINE 6

I, Carl Todd, do hereby certify that the above log is true and correct to the best of my knowledge and belief.

Carl Todd