

RECEIVED
STATE CORPORATION COMMISSION

Form CP-4
Rev. 12-15-80

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

SEP 2 1982

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 12 TWP. 33 RGE. 12W E/W
Location as in quarters or footage from lines:
C SE SE

Locate Well
correctly on above
Section Platt.

Lease Owner Okmar Oil Company
Lease Name Harbaugh B #2 Well No. _____
Office Address Box 723 Hays, Kansas 67601
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 8-13-82
Plugging completed 8-26-82
Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz
Producing formation _____ Depth to top _____ bottom T.D. 4506'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	240'	none
				4-1/2"	4506'	2776'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Water flowing out surface, pumped 40 sacks weight mud down 8-5/8" and pumped
25 sacks cement down 4-1/2" and pumped plug to 4200'. Shot casing @3608', 3436',
3221', 3008', 2804', pulled 55 joints of 4-1/2", pumped 10 sacks weight mud down
4-1/2", pulled 11 joints. Plugged well with 5 sacks hulls, 25 sacks gel, 8-5/8"
plug, 200 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 19 82

My Commission expires:



Irene Hoover
Notary Public.

HARBAUGH B-2.
Okmar Oil Company
Hays, Kansas

August 13, 1975

Sec. 12 T. 33 R. 12W Elev. _____ County Barber Co, Ks.

TD Washed down 4506 Zero Point 5' AG

Casing 4½ @ 4505

Shoe Joint 33.64

Ran 108 joints 10.50# New 4½ casing
Tally 4512' threads off.
Cemented w/ 100sx 60/40 Posmix 18% salt

Left 3 joints @ location tally 127.
Threads off

One 4½ reg Guide Shoe
One 4½ Insert Float
3 4½ Centralizers
One Cont. Bakelock

OKMAR OIL CO. #2 HARBAUGH "B" OWWO 12-33-12W
 970 FOURTH FINANCIAL CTR. C SE SE
 CONTR B & B DRILLING CTY BARBER

GEOL _____ FIELD RHODES.

e 1394 RB CM 1976 CARD ISSUED 7/21/77 IP OF 100 MCFGPD
 MISS 4408-40

+	+	+
+	+	+
+	+	+

API

TOPS	DEPTH	DATUM
HEEB	3566	-2172
TOR	3594	-2200
B/OREAD	3657	-2263
DOUG SD	3698	-2304
LANS	3742	-2348
MISS	4402	-3008
ID	4507	-3113

OLD INFO: WAS GRAHAM-MICHAELIS PTD 4500
 #1 HARBAUGH, 8"239, D&A/3/29/57
 DST (1) 3570-93/1½', 188'GSY MD, BHP 265
 DST (2) 4407-27/1½', G/11", 105'GCM,
 BHP 1555#
 DST (3) 4427-49/1½', G/32", 70'GCM, BHP
 1650#

NEW INFO: SET 4½" 4506, PF (MISS)
 4408-40, AC 1500, FRAC'D, REC LD, SI

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS