


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 1 Twp. 33S Rge. 11 R/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW NE

Lease Owner Kansas Oil Corporation
Lease Name HARBAUGH Well No. 1
Office Address 400 N. Woodlawn, Suite #2, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 07-15 1980
Application for plugging filed 07-15 1980
Application for plugging approved 07-15 1980
Plugging commenced 07-15 1980
Plugging completed 07-15 1980

Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4578'

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 4578'
Set 1st plug at 270' with 50 sx.
2nd plug at 40' solid bridge.
Rathole with 5 sx. 50/50 posmix, 6% gel.
Plug was down at 1:45 p.m. 07-15-80.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 1980

My commission expires _____



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR: Kansas Oil Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: HARBAUGH #1
 LOCATION: NW NW NE, Section 1-33S-11W, Barber County, Kansas
 SPUD DATE: 07-07-80
 COMPLETION DATE: 07-15-80

0	255	Red Bed
255	640	Red Bed & Shale
640	4578	Lime & Shale
	4578	Rotary Total Depth

Spud hole at 6:45 p.m. on 07-07-80. Drilled 250'. Ran 6 joints of new 8-5/8" - 20# casing (Tally 239'). Set @ 249' with 175 sx. of common cement, 2% gel, 3% c.c. Cement did circulate. 4-1/2 hours drilling, 3/4 hour repairs, t hours waiting on cement, 2-1/4 hours pipe job. Job completed at 2:00 a.m. 07-08-80.

T.D. 4578'. Set 1st plug at 270' with 50 sx., 2nd plug at 40' solid bridge. Rathole with 5 sx., 50/50 posmix, 6% gel. Plug was down at 1:45 p.m. 07-15-80.

SAMPLE TOPS:

Anhydrite 1270

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 24 1980
 CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the HARBAUGH #1, NW NW NE, Section 1-33S-11W, Barber County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 22nd day of July, 1980.

Sherrie L. Brooks
 Sherrie L. Brooks, Notary Public

