

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber

County, Sec. 2 Twp. 33S Rge. (X) 11 (W)

Location as "NE/CNW/SW" or footage from lines 1165' NSL & 990' EWL SW/4

Lease Owner Gulf Oil Corporation

Lease Name Lloyd Davis Well No. 1

Office Address Box 661, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-5 19 57

Application for plugging filed 2-5 19 57

Application for plugging approved 2-5 19 57

Plugging commenced 2-5 19 57

Plugging completed 2-5 19 57

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top: Bottom Total Depth of Well 1600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	252	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 250'. Placed wooden plug at 250' and dumped 1/4 sack hulls on plug. Spotted 35 sacks cement on hulls. Filled hole with mud to 35' and set wooden plug. Dumped 1/4 sack hulls on plug. Capped with 15 sacks cement filling hole to base of cellar.

NOTE: Attached is Driller's Formation Record which is being filed in accordance with your instructions.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 2 - 1957  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Musgrove Petroleum Corporation, Inc.  
Address 801 Union Center Building, Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Thomas A. Trax (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas A. Trax, Asst. Zone Supt. of Prod.  
Box 2233, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of February, 19 57

My commission expires 2-4-59

Ray W. Rowell Notary Public.

JRM:BJT

PLUGGING  
FILE SEC 2 T 33 R 11W  
BOOK PAGE 179 LINE 8

CONTRACTOR'S WELL LOG

COMPANY:	Gulf Oil Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	Lloyd Davis #1
LOCATION:	NE SW SW, Sec. 2-33-11W Barber County, Kansas
COMMENCED:	January 21, 1957
COMPLETED:	February 5, 1957

0	253	Sand & red bed
253	1100	Shale & shells
1100	1560	Shale & lime streaks
1560	3730	Shale & lime
3730	3840	Sand & shale
3840	4440	Lime
4440	4510	Lime & shale
4510	4544	Lime
4544	4576	Lime & chert
4576	4600	Lime
	4600	Rotary Total Depth

Set 8-5/8" surface at 252' with 250 sacks cement.

Dry and Abandoned.

ELEVATION:	1538' D. F.	TOPS:	
	1540' K. B.	Heebner	3645' (-2105)
		Douglas	3740' (-2200)
		Brown Lime	3824' (-2284)
		Lansing/Kans. City	3838' (-2298)
		Miss. Chert	4498' (-2958)
		Miss. Lime	4501' (-2961)

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the LLOYD DAVIS #1, NE SW SW, Section 2-33-11W, Barber County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Emil E. Bowers  
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 13th day of February, 1957.

Leah Anne Helke  
Notary Public

My commission expires June 16, 1959.

RECEIVED  
CORPORATION COMMISSION  
MAR 2 1957  
WICKI  
PLUGGING  
FILE SEC 2 T-3 R/W  
BOOK PAGE 139 LINE 8