

TYPE OR PRINT
 NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

2580 Ft. from S Line of Section (circle one)

550 Ft. from E W Line of Section (circle one)

LEASE OPERATOR McGinness Oil Co.

SPOT LOCATION NW - NW - SW

ADDRESS 150 N. Main Suite 1026

SEC. 3 TWP. 33S. S. RGE 11 (X) (X) (W)

CITY, STATE, ZIP Wichita, ks. 67202

COUNTY Barber

PHONE# (316) 267-6065 OPERATORS LICENSE NO. 5255

Date Well Completed _____

Charater of Well Gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 12-1-95

Date Plugging Completed 12-21-95

The plugging proposal was approved on 12-18-95 (date)

by Richard Lacey - Dodge City, Kansas. (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation(s) _____ Depth to Top PBTD 3718 T.D. 4540
 Bottom

Show depth and thickness of all water, oil and gas formations. Perfs: 3704.5 - 3711.5.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	<u>8 5/8</u>	<u>0</u>	<u>227'</u>	<u>8 5/8</u>	<u>227'</u>	<u>0</u>
	<u>4 1/2</u>	<u>0</u>	<u>3810</u>	<u>4 1/2</u>	<u>3810'</u>	<u>3777' - 7 1/2 ft.</u>

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

12-1-95: Layed down 144 x 5/8 rods and 114 x 2 3/8 tbg. Dumped sand to soft above perfs, then 4sx. cement. Sand at 3600ft. fluid 200ft. from surface.

12-2-95: Shot off casing and layed down 77 ft. of 4 1/2 casing. (over)
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

RECEIVED
 STATE CORPORATION COMMISSION

License No. 5893

DEC 26 1995

Address Box 847 Pratt, ks 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McGinness Oil

STATE OF Kansas COUNTY OF Pratt

Julia Berry ^{SS.} plugging contractor
 (Employee of Operator or ~~Operator~~ of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Julia Berry



(Address) PO PWA Inc.

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 19 1995

Dorothy M. Furgason
 Notary Public

My Commission Expires Feb. 6, 1997

12-21-95

Wells

0 0
0 0

WZ WU WY
WZ WU WY
WZ WU WY

XX

Wells
Wells
Wells
Wells
Wells

12-21-95: Allied pumped 300# hulls - 10sx. gel - 50 sx.
cement - 10sx gel - 100# hulls - Plug - 100sx. cement.
60-40 poz. 6% gel. Max. pressure 100#. ISIP 500#.

