

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-005-01043-00-00

API NUMBER N/A - 5/28/56

LEASE NAME INSLEE "A"

WELL NUMBER #1

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 3 TWP. 33S RGE. 11 (E) or (W)

COUNTY BARBER

Date Well Completed 5-28-56

Plugging Commenced 10-1-87

Plugging Completed 10-2-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CHEVRON U.S.A. Inc.

ADDRESS P.O. Box 12116

PHONE# (405) 949-7000 OPERATORS LICENSE NO. 4519

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 27, 1987 (date)

by SHARI FEIST - DIRECTOR (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation DOUGLAS Depth to Top 3679 Bottom 3685 T.D. 4516

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>DOUGLAS (RECOM)</u>	<u>GAS</u>	<u>SURF</u>	<u>280</u>	<u>8 5/8</u>	<u>280'</u>	<u>0</u>
		<u>SURF</u>	<u>4516</u>	<u>5 1/2</u>	<u>4516'</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Circ hole w/ 9.0 ppg mud. RIH w/ CIBP @ 3420'. RIH w/ Dump bailer. Dump 25K cmt on top of same. RIH w/ 4" csg guns & perf 5 1/2" csg @ 750' w/ 4 c/pf. Est Circ Down 5 1/2" Flap annulus. Pump 333 sx cl "A" cmt, 15.6 ppg. Left 5 1/2" full of cmt. Cut csg 6' BGL. CAP & ID well. P&A Complete. Steve Durant KCC approved procedure

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B J TITAN License No. N/A

Address P.O. Box 368

STATE OF KANSAS COUNTY OF BARBER, ss.

DANIEL L. JORDAN (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Daniel L Jordan

(Address) P.O. Box 12116 OKLA. CITY, OK 73157

SUBSCRIBED AND SWORN TO before me this 4th day of NOVEMBER, 19 87

Steve Durant
Notary Public

My Commission Expires: 9-16-89

NOV 5 1987