

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barber

County. Sec. 9 Twp. 33S Rge. 12 (W)

Location as "NE/CNW/SW" or footage from lines Ctr. SW 1/4 SW 1/4 NE 1/4

Lease Owner Monsanto Chemical Company

Lease Name Jarnigan Well No. 1

Office Address P. O. Box 639, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 17 19 56

Application for plugging filed (Verbal) January 17 19 56

Application for plugging approved (Verbal) January 17 19 56

Plugging commenced January 17 19 56

Plugging completed January 17 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5015' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	316'	N one

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from 5015' to 300'.
Halliburton Plug @ 300' with
20 sack cement. Heavy mud
from 300' to 35'. Set top
plug @ 35' with 1/4 sack of hulls
and 10 sacks of cement on top
of plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Messman-Rinehart Drilling (License No. 20)

Address 1005 East Second, Wichita, Kansas

STATE OF KANSAS, COUNTY OF PRAIT, ss. J. B. Gibbs

(employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

P. O. Box 639, Pratt, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of January, 19 56

My commission expires September 19, 1959

Notary Public.

PLUGGING
FILE SEC 9 T 33 R 12 W
BOOK PAGE 32 LINE 27

RECORDED
STATE CORPORATION COMMISSION
JAN 19 1956
CONSERVATION DIVISION
Wichita, Kansas

NO. 1 JARNIGAN

WELL RECORD

Location: SW SW NE, 9-33S-12W
Barber County, Kansas

Commenced: December 31, 1955

Operator: Monsanto Chemical Company
Lion Oil Company Division
211 W-K-H Building, Wichita, Kansas

Completed: January 17, 1956

Elevation: 1536 KB (1526 Gr)

Production: D&A

Contractor: Graham-Messman-Rinehart Drilling Co.
1005 East Second, Wichita, Kansas

Casing Record: 8 5/8" @ 316' w/250 sacks cement

.....L O G.....

Surface Soil	30
Red Bed	317
Red Bed-Shale-Gyp	1260
Shale	1750
Shale-Lime	2367
Lime-Shale	2602
Shale	2652
Lime-Shale	2827
Shale-Lime	3238
Lime-Shale	3357
Shale-Lime Strks	3570
Shale-Lime	3991
Lime	4220
Lime-Shale	4312
Lime	4346
Lime-Shale Strks	4450
Lime-Chert	4474
Mississippi	4533
Lime-Shale	4577
Lime	4620
Mississippi	4756
Lime-Shale	4791
Lime-Chert	4857
Lime-Chert	4865
Coring	4915
Lime-Shale	4964
Lime-Shale	4990
Arbuckle	5015 R.T.D.

Sample Tops:

Doug Sd 3766 (-2230)
 K. C. 3850 (-2314)
 Miss. 4455 (-2919)
 Viola 4760 (-3224)
 Simpson 4862 (-3326)
 Arbuckle 4985 (-3449)

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me this 23rd day of January 1956.

Juanita L. Louis
Notary Public

My Commission Expires: November 5, 1958

RECEIVED
STATE CORPORATION DIVISION
FEB 29 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 9 T 33 R 12W
BOOK PAGE 32 LINE 27