


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 27 Twp. 30 Rge. 14 ~~28~~ (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Purcell Mull Drilling Co.
Lease Name Pickens Well No. 1
Office Address 6405 E. Kellogg, Wichita, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8/10/55 19
Application for plugging filed 8/10/55 19
Application for plugging approved " 19
Plugging commenced " 19
Plugging completed " 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4725 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Water	3806			375	None
Toronto	"	3851				
Brown Lime	"	3996				
Mississippi	"	4428				
Viola	"	4558				
Simpson	"	4697				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled Hole w/ Heavy Mud to 250'

Set cement Plug at 250' using 15 sacks cement 1/2 sack Hulls

Filled Hole to 30' w/ heavy Mud

Set cement Plug using 10 sacks of cement 1/2 sack Hulls

Cement to bottom of Cellar

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1955
8-31-55
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Iron Drilling Company
Address 1206 Philtower Bldg., Tulsa, Okla.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
J. L. Stackpole (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Stackpole
Tulsa, Okla.
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of August, 19 55

My commission expires Feb. 28, 1956

Notary Public.

PLUGGING
FILE SEC 27 T 30 R 14 W
BOOK PAGE 142 LINE 2

15-007-00192-0000
 DRILLING RECORD

Well No. 1 Pickens
 NE NE NW, Sec 27-30-14W
 Barber County, Kansas

Casing Record

375' of 8-5/8" OD Surface Pipe
 cemented with 300 sacks.

Well Commenced 7/22/55
 Drilling Commenced 7-24-55
 Drilling Completed ~~8-10~~ 8-10-55
 Well Completed 8-11-55

No Oil String -- Dry Hole

WELL LOG

Surface Clay & Shale	0 to 45
Sand	45 to 70
Sand & Shale	70 to 105
Red Bed	105 to 856
Shale & Shells	856 to 1200
Shale & Shells	1200 to 1730
Shells	1730 to 1810
Shale & Shells	1810 to 1935
Shale	1935 to 1965
Lime, Shale & Shells	1965 to 2100
Lime & Shale	2100 to 2635
Lime	2635 to 2750
Lime & Shale	2750 to 2925
Shale	2925 to 3088
Broken Lime	3088 to 3171
Lime	3171 to 3200
Lime & Shale	3200 to 3300
Lime & Shale	3300 to 3395
Lime	3395 to 3470
Lime & Shale	3470 to 3560
Lime	3560 to 3635
Lime & Shale	3635 to 3720
Lime & Shale	3720 to 4075
Lime	4075 to 4428
Broken Lime	4428 to 4478
Lime	4478 to 4550
Lime & Shale Cherty	4550 to 4580
Lime & Shale	4580 to 4610
Shale & Chert	4610 to 4645
Broken Lime Chert	4645 to 4685
Lime, Chert & Shale	4685 to 4696
Simpson	4696 to 4725 TD

VED
 COMMISSION

8-31-55
 DIVISION

PLUGGING
 FILE SEC 27 T 30 R 14 W
 BOOK PAGE 142 LINE 2