


15 007-0530-00-01

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County Sec 28 Twp 30 Rge 14 (E) (W)



Locate well correctly on above  
Section Plat

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NE  
Lease Owner J. M. Huber Corporation  
Lease Name Werner #C Well No. 1  
Office Address 916 South Pine - Pratt, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Old Well Worked over  
Date well completed March 11, 1950 19  
Application for plugging filed March 25, 1950 19  
Application for plugging approved March 26, 1950 19  
Plugging commenced March 26, 1950 19  
Plugging completed March 29, 1950 19  
Reason for abandonment of well or producing formation Dry Hole  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough - Great Bend  
Producing formation Depth to top Bottom Total Depth of Well 4520 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"	4518'	2441'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Lane-Wells Plug set at 3270'  
Perforated from 3186 to 3204'  
Plugged back from 3270 to 3180' w/crushed rock  
Dumped 5 sacks cement at 3180'  
Heavy mud to 250'  
Dumped 15 sacks cement on 10' rock bridge at 250'  
Heavy mud to 30'  
10 sacks cement to bottom of cellar

RECEIVED

Conservation  
4-10-50  
APR 10 1950

STATE OF KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. M. Huber Corp.  
Address Box 460  
Pratt, Kansas

STATE OF KANSAS COUNTY OF PRATT SS.  
I, J. L. Kyler, employee (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN to before me this 8th day of April 19 50

J. L. Kyler  
Notary Public.

My commission expires August 20, 1951

PLUGGING  
FILE SEC 28 T 30 R 14 (E)  
BOOK PAGE 145 LINE 28

COMPANY: J. M. HUBER CORPORATION (Was Great Lakes) LOCATION: NW NW NE  
CONTRACTOR: PABCO DRILLING CO. 28-30S-14W  
Barber County, Ks  
FARM NAME: Werner "C" #1  
COMMENCED: 2-6-50  
COMPLETED: 3-11-50 PRODUCTION: D & A

OLD WELL WORKED OVER

Old Total Depth 4531  
Sand 4531-3542 Total Depth

Swabbed through casing approx. 3 barrels water per hr for 6 hours through perforations 4067-74. Squeezed perforations w/200 sacks cement. Drilled out cement to 4531, original total depth. Tested 2 1/2 bbls. salt water per hr with small show of gas, no oil.  
Drilled deeper to 4538, show oil in samples 4533-38. Tested 3 bbls. water and 1/4 bbl oil per hr at 4538. Drilled deeper to 4541. Swabbed 60 1/2 bbls. water, 2 1/2 bbls. oil/8 hours.  
Set Lane-Wells Plug at 3850'.  
Perf. casing w/4 shots 3810-11, found no cement behind pipe. Squeezed w/150 sacks cement. Drilled cement to 3807.  
Perf. 12 shots 3793-97, good show gas.  
Perf. casing with 39 shots 3780-93, gas increase about double. Acidized w/500 gal acid thru casing, swabbed 2 3/4 barrels water plus 1 1/2 gal oil per hr for 4 hours, 76 MCF gas. Swabbed a total of 13.31 barrels water plus 4.07 bbls. oil next 12 hrs., gas volume 124 MCF.  
Treated w/2000 gal acid thru casing, swabbed 26 bbls. water plus 8 bbls. oil for 6 hrs, 224 MCF gas. Swabbed 7 1/2 plus 3 1/2 bbls. oil for 24 hrs, gas volume 224 MCF.  
Set Lane-Wells Plug at 3600'.  
Perf. casing w/15 shots 3564-69, 7 to 10 bbls. water per hr.  
Set Lane-Wells Plug at 3557'.  
Perf. Casing w/13 shots 3542-46, 7 to 10 bbls. water per hr.  
Perf. casing w/18 shots 3520-26, no increase, no shows.  
Set Lane-Wells Plug 3495 1/2'.  
Perf. 18 shots 3454-60, swabbed 5 bbls. salt water per hr for 2 hrs., no shows, squeezed perf. w/200 sacks cement. Cleaned out to Lane-Wells Plug at 3495 1/2'.  
Perf. casing w/43 shots 3446-60, no shows, acidized w/500 gals. swabbed 5 1/2 barrels salt water per hr for 3 hrs. no shows.  
Set Lane-Wells Plug at 3370'.  
Perf. 4 shots 3319-20.  
Perf. 2 shots 3347-48 no cement job. Squeezed w/150 sacks cement, drilled cement to 3340, tested 1 barrel salt water per hr.  
Set Lane-Wells Plug 3270'.  
Perf. 55 shots 3186-3204, no shows, acidized w/1000 gallons. swabbed 1 3/4 bbls. salt water per hr for 6 hrs., no shows. D&A

4-10-50  
APR 10 1950

STATE OF KANSAS  
CORPORATION  
KANSAS

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

PLUGGING  
FILE SEC 21 30 R 120  
BOOK PAGE 145 LINE 28

I hereby certify that the above is a true and correct copy of the log of the Werner C-1 located in the Northwest Quarter of the Northwest Quarter of the Northeast Quarter (NW NW NE) of Section 28-30S-14W of Barber County, Kansas

Signed: \_\_\_\_\_  
E. A. Huffman Dist. Manager  
J. M. Huber Corporation

Subscribed and sworn to before me this 24 day of March, 1950

Commission Expires: Jan 26, 1953  
Dorothy J. Reves  
Notary Public