


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ness County, Sec. 23 Twp. 20S Rge. (E) 22 (W)  
Location as "NE/CNW/SW" or footage from lines Approx. C NE NE  
Lease Owner Rains & Williamson Oil Co.  
Lease Name GOATLEY Well No. 1  
Office Address 1425 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 2 1964  
Application for plugging filed November 2 1964  
Application for plugging approved November 2 1964  
Plugging commenced November 2 1964  
Plugging completed November 2 1964  
Reason for abandonment of well or producing formation no oil or gas found  
in commercial quantities.  
If a producing well is abandoned, date of last production - - 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4390 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
				8-5/8"	325'	325'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug @ 540', cement thru drill pipe with 20 sacks, mud back to 300', set plug and hulls, cement thru drill pipe with 20 sacks, mud back to 40', set plug and hulls and capped with 10 sacks cement, 2 sacks in rathole. Plug down 11:45 a.m. 11-2-64.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 5 1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Wilson Rains (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
Wilson Rains  
1425 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of November, 19 64

My commission expires January 8, 1968  
Shirley Keck  
Shirley Keck Notary Public.

ROTARY DRILLING LOG

15735-19/60-0000

Operator: Rains & Williamson Oil Co.  
 No. 1 GOATLEY  
 Approximate C NE NE  
 Section 23-20S-22W  
 Ness County, Kansas

Contractor: Rains & Williamson  
 Oil Co.

Commenced: 10-23-64

Completed: 11-2-64

Remarks: Set 325' 8-5/8" surface casing with 180 sacks cement.

Formations

Surface Clay & Post Rock	45'
Shale	326'
Shale & Red Bed	776'
Anhydrite	785'
Shale	865'
Dakota Sand	1075'
Shale	1428'
Anhydrite	1464'
Shale	1900'
Shale & Lime Streaks	2125'
Lime & Shale	2710'
Shale & Lime	2875'
Lime & Shale	3175'
Shale & Lime	3710'
Lime & Shale	4390'
 Rotary Total Depth (D&A)	 4390'

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 5 1964

CONSERVATION DIVISION  
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 4th day of November, 1964.

My Commission Expires:  
 January 8, 1968

*Shirley Keck*  
 Shirley Keck, Notary Public