

API NUMBER 15-135-21,935-0000

LEASE NAME Barricklow

WELL NUMBER 3 S.W.D.W.

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 20 TWP. 20S RGE. 22 (X) or (W)

COUNTY Ness

Date Well Completed 4/3/81

Plugging Commenced 12/5/85

Plugging Completed 12/5/85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Mid-Continent Energy Corporation

ADDRESS 120 S. Market, Suite 310 - Wichita, KS 67202

PHONE#(316) 265-9501 OPERATORS LICENSE NO. 5205

Character of Well S.W.D.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6 - Dodge City, KS

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top 4785' Bottom 4880+ T.D. 4880'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	Water	Surface	531	8-5/8"	531	None
Mississippi	Water	Surface	4785	4 1/2"	4785	None

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plug 4 1/2" w/ 50 sks. 60/40 POZ (6% gel) then 15 sks. gel, 1 sk. HULLS & 4 1/2" wiper plug then 130 sks. 60/40 POZ. 5 sks. gel & 175 sks. 60/40 POZ (6% gel) down backside.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mid-Continent Energy Corporation License No. 5205

Address 120 S. Market, Suite 310 - Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Kent R. Roberts (Employee of Operator) ~~or Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Kent R. Roberts

(Address) Kent R. Roberts
 120 S. Market, Suite 310 - Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 1986

Mary Kathleen Bachman
 Notary Public

My Commission Expires: _____



RECEIVED
 STATE CORPORATION COMMISSION

JAN 3 1986
 1-3-86
 CONSERVATION DIVISION
 Wichita, Kansas