

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-21,671-0000

LEASE NAME Barricklow

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 20 TWP. 20 RGE. 22 (E) or (W)

COUNTY Ness

LEASE OPERATOR Mid-Continent Energy Corporation

ADDRESS 155 N. Market #200

Date Well Completed 10-12-79

PHONE#(316) 265-9501 OPERATORS LICENSE NO. 5205

Plugging Commenced 8-18-89

Character of Well Oil

Plugging Completed 8-18-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 18, 1989 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4350 Bottom 4352 T.D. 4460

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Oil & Water	surface	491'	8 5/8"	491	none
		surface	4460'	4 1/2"	4460	2128'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer, 2nd plug pumped 300 lbs. hulls; 10 sx gel; 50 sx cement; 13 sx gel; 100 lbs. hulls; and 150 sx cement down 8 5/8". Maximum pressure 1200 psi and shut in 300 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pluggers, Inc. License No. 3908

Address P.O. Box 782050, Wichita, Kansas 67278

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pluggers, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Bradley R. Buehler (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bradley R. Buehler

(Address) Bradley R. Buehler
155 N. Market #200 Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 17 day of November, 19 89



My Commission Expires

Notary Public