

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-21,748-0000

LEASE NAME Brennan

WELL NUMBER #1

4620 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 19 TWP. 20 RGE. 22 (E) or (W)

COUNTY Ness

Date Well Completed 6-6-81

Plugging Commenced 8-18-89

Plugging Completed 8-18-89

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mid-Continent Energy Corporation

ADDRESS 155 N. Market #200

PHONE# (316) 265-9501 OPERATORS LICENSE NO. 5205

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 18, 1989 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4345 Bottom 4347 1/2 T.D. 4420

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	oil & water	surface	530'	8 5/8"	530'	none
		surface	4419'	4 1/2"	4419'	2112'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 1st plug sanded back to 4295' and dump 4 sx cement on top of sand through bailer, 2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 13 sx gel, 100 lbs. hulls, and 150 sx cement down 8 5/8". Maximum pressure 700 psi and shut in 200 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pluggers, Inc. License 3909

Address P.O. Box 782050, Wichita, Kansas 67278

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pluggers, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. CONSERVATION DIVISION

Bradley R. Buehler (Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bradley R. Buehler

(Address) 155 N. Market #200 Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 16 day of November, 19 89

My Commission Expires _____



Gayle Nye
Notary Public