

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas, 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barber SEC. 12 TWP. 33 RGE. 12W E/W  
Location as in quarters or footage from lines:  
SW SW NE

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Locate Well  
correctly on above  
Section Platt.

Lease Owner Okmar Oil Company  
Lease Name Harbaugh C-1 Well No. \_\_\_\_\_  
Office Address 970 Fourth Financail Center, Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 5-13-83  
Plugging completed 6-24-83  
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4425'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size   | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 270'   | none       |
|           |         |      |    | 5-1/2" | 3635'  | 2792'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Pumped bottom with 30 sacks cement, plug stopped @3300'. Shot casing @2901'  
and 2811', pulled a total of 71 joints (2792') of 5-1/2" casing. Plugged well  
with 5 hulls, 15 gel, 50 cement, 10 gel, 8-5/8" plug and 100 sacks cement.

Plugging Complete

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 19 83

My Commission expires:



Irene Hoover  
RECEIVED Notary Public.  
STATE CORPORATION COMMISSION

JUN 28 1983

DRILLERS' LOG

OKMAR OIL COMPANY  
No. 1 Harbaugh 'C'  
SW SW NE, Sec. 12-33S-12W  
Barber County, Kansas

Elevation: 1410 K.B.

Commenced: 11-27-72  
Completed: 12-9-72

Surface Casing: 270' of  
8-5/8" cemented w/250 sx  
60-40 Posmix, 3% cc.  
11-28-72

| <u>FORMATION</u>       | <u>DEPTH</u>     |
|------------------------|------------------|
| Clay & Sand            | 0 - 35           |
| Red Rock & Shale       | 35 - 975         |
| Blaine Anhydrite       | 975 - 996        |
| Shale                  | 996 - 1280       |
| Stone Corral Anhydrite | 1280 - 1300      |
| Lime & Shale           | 1300 - 2225      |
| Lime                   | 2225 - 3490      |
| Lime & Shale           | 3490 - 3600      |
| Lime                   | 3600 - 4360      |
| Lime & Chert           | 4360 - 4399      |
| Lime                   | 4399 - 4425 T.D. |

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 13th day of December, 1972.

My Commission Expires:  
August 25, 1976

*Ella Priess*  
Ella Priess, Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

APR 28 1983

CONSERVATION DIVISION  
Wichita, Kansas