

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 24 Twp. 33S Rge. 12W (E) W (W)

Location as "NE/CNW&SW&" or footage from lines NE SW SE

Lease Owner The Superior Oil Company

Lease Name Harbaugh Unit Well No. 1

Office Address Box 690, Chickasha, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Non-Commercial Gas Well

Date well completed March 8 19 57

Application for plugging filed January 2, 1958 19 58

Application for plugging approved January 3, 1958 19 58

Plugging commenced January 3, 1958 19 58

Plugging completed January 7, 1958 19 58

Reason for abandonment of well or producing formation Non-Commerical

If a producing well is abandoned, date of last production No sales 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. J. Lewis Brock and Mr. LaKamp

Producing formation Mississippi Depth to top 4526 Bottom 4578 Total Depth of Well 4630 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Gas	4538	4578	10-3/4"	332'	None
				7"	4630'	3262 Ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Placed 75 sack (Portland Regular Cement) plug from 4222 to 4585. (Perfs: 4538-43, 4552-56)

Pulled 3262' 7" Casing. Casing cut off at 3262. (Perfs: 4564-78)

Loaded hole with mud.

Placed 75 sack cement plug from 195 to 342 ft.

Placed 15 ft. cement plug at top of surface casing.

Welded steel cap on top of surface casing.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 9 1958

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Toland and Reeves

Address 1315 S. E. 29th St. Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Grady, ss.

Wm. N. Mosley, Dist. Engineer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wm. N. Mosley

Box 690, Chickasha, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 8th day of January, 19 58

My commission expires Sept. 15, 1960

M. F. Fiegel Notary Public.

PLUGGING  
FILE SEC 24 T 33 R 12 W  
BOOK PAGE 73 LINE 24

HARBAUGH UNIT NO. 1

NE SW SE Sec. 24-33S-12W  
Barber County, Kansas  
The Superior Oil Company

10-3/4" O. D. casing cemented at 332'  
7" O. D. casing cemented at 4630'

Drilling commenced November 12, 1956  
Drilling completed December 4, 1956

FROM	TO	FORMATION	REMARKS
0'	99'	Sand & clay	
99	332	Red bed	10-3/4" O. D. casing cemented at 332'
332	370	Red bed & shale	
370	695	Shale	
695	1050	Shale & anhydrite	
1050	1410	Anhydrite & shale	
1410	1620	Shale & lime	
1620	1738	Lime	
1738	1825	Lime & shale	
1825	1855	Lime	
1855	2850	Lime & shale	
2850	2935	Shale & lime	
2935	3019	Lime & shale	
3019	3161	Lime	
3161	3255	Lime & sand	
3255	3561	Lime & shale	
3561	3623	Lime, shale & pyrite	
3623	3737	Lime & shale	
3737	3762	Lime	
3762	3853	Sandy lime & shale	
3853	3858	Lime & shale	
3858	4375	Lime	
4375	4473	Lime & shale	
4473	4575	Lime & chert	
4575	4623	Chert, lime & shale	
4623	4630	Cherty lime	7" O. D. casing cemented at 4630'

T.D. 4630'

STATE OF KANSAS  
WICHITA COUNTY

JAN 5 1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 24 T 33 R 12W  
BOOK PAGE 73 LINE 24