

WELL PLUGGING RECORD

Rush

County. Sec. 25 Twp. 19 Rge. (E) 16 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW/4 SW/4 SW/4

Lease Owner Berwick Spruill Harms, Inc.

Lease Name Conrad-Tamman

Well No.1

Office Address: Box 184, Great Bend, Kans

Character of Well (completed as Oil, Gas or Dry Hole) OIL & GAS

Date well completed.....3-14.....1948

Application for plugging filed 3-16 1949

Application for plugging approved 4-20 1949

Plugging commenced 4-23 1949

Plugging completed. 4-26 1949

Reason for abandonment of well or producing formation not paying quantity

If a producing well is abandoned, date of last production..... 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, of Great Bend, Kans

Producing formation Arbuckle Depth to top 3658 Bottom Total Depth of Well 3714 Feet

Show depth and thickness of all water, oil and gas formations.

OIL GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, fromfeet tofeet for each plug set.

Lanewell bridging Plug set at 3700 Ft.

Top perforation at 3660 ft.

Filled hole to 3650 with mud; put in 5 sacks cement. Pulled 3065 ft of pipe, mudded to 250 ft. Put in rock bridge, 15 sacks cement; mudded to 30 ft., put in 10 sacks cement which filled hole to top.
(Put in rock bridge)

RECEIVED
Conservation Div.
S-5-49
MAY 5 - 1949
STATE CORPORATION
COMMISSION
KANSAS
this sheet

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to:

Address.

STATE OF Kansas COUNTY OF Barton ss

.....(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of May, 1946

My commission expires Oct - 15 1981

Notary Public

PLUGGING
FILE SEC 2 5 19 R 16W
BOOK PAGE 94 LINE 4

151165-01836-0000

WELL LOG

BERWICK, SPRUILL, HARMS, INC.
Conrad #1

SEC.25 T.19 R.16W
C. SW/4 SW/4 SW/4
County: Rush

Total Depth: 3710'
Comm: 2-20-48 Comp: 3-4-48
Contractor: Berwick, Spruill, Harms, Inc.
Issued: 4-16-48 Rotary: O-3710'

CASING:

8 5/8" 1027' cem.
6" 3709' cem.

Elevation: 1976'
Production:

Figures Indicate Bottom of Formations.

cellar 0-5
shale & shells 400
sand 655
redbed & shells 1008
Anhydrite 1040
redbed, shale,
& shells 1440
shale & shells 1530
salt 1690
shale & lime 3475
lime 3710
T.D. 3710

Tops:

Anhydrite 1008

We hereby certify this to be an accurate and correct log of the above described well as shown by the daily drilling reports.

BERWICK, SPRUILL, HARMS, INC.

BY: *[Signature]*

Subscribed and sworn to before me this 4th day of May 1948.

My Commission expires:

Oct 15, 1951

[Signature]
NOTARY PUBLIC

RECEIVED

Conservation Div.
5-5-49
MAY 5 - 1949

STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
FU SEC 25 T 19 R 16W
COOK PAGE 94 U 4