

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-165-21282-0000

LEASE NAME Tammen

WELL NUMBER 1-24

C of E/2 SW SW  
SPOT LOCATION \_\_\_\_\_

SEC. 24 TWP. 19S RGE. 16W(E) or (W)

COUNTY Rush

Date Well Completed \_\_\_\_\_

Plugging Commenced 6-2-86

Plugging Completed 6-9-86

LEASE OPERATOR Helmerick & Payne, Inc

ADDRESS P.O. Box 394 Plainville, Kansas 67663

PHONE # (316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3730'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1031'	none
				5-1/2"	3728'	2869'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 3174' and 5 sacks cement. Shot pipe @3100', 3000', 2869', pulled a total of 73 joints of 5-1/2" casing. Plugged surface with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8-5/8" plug and 150 cement, 60/40 pos. 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

RECEIVED  
STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Rice, ss. JUN 23 1986

R. Darrell Kelso (employee of operator) of 6-23-86  
(operator) of above-described well, being first duly sworn on oath, says: That CONSERVATION DIVISION  
I have knowledge of the facts, statements, and matters herein contained and Wichita, Kansas  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) R Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 19th day of June, 19 86



Irene Hoover  
Notary Public

My Commission expires: \_\_\_\_\_