

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

BARBER

County. Sec. 32 Twp. 33 Rge. 12W (X) (W)

Location as "NE/CNW/SW" or footage from lines NW SW SW

Lease Owner Petroleum, Inc.

Lease Name McCracken Unit Well No. 1

Office Address Route 2, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 19, 19 57

Application for plugging filed August 14, 19 58

Application for plugging approved August 18, 19 58

Plugging commenced September 15, 19 58

Plugging completed September 18, 19 58

Reason for abandonment of well or producing formation No Producing Zones

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Lackamp, Stafford, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4679' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258'	None
				5-1/2"	4722'	3625'
Mississippi	Water and little gas	4600'	4612'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with crushed rock from 4679' to 4590' followed by 5 sacks cement. Globe Oil Well Cementing Company pumped in 50 sacks gel. Mudded up to 258 feet and made solid rock bridge on top of mud. Placed 20 sacks cement on top of rock bridge. Mud up to 35' and made solid rock bridge. Placed 10 sacks cement on top of rock bridge to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service
Address 102 West 18 th Street, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF BARTON
DON SEARLE ss.

(employee of owner) or ~~(Notary Public)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

ROUTE 2, GREAT BEND, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 20 th day of SEPTEMBER

My commission expires July 11, 1960

RECEIVED
STATE CORPORATION COMMISSION

Notary Public.
SEP 23 1958

PLUGGING
FILE SEC 32 T 33 R 12W
BOOK PAGE 123 LINE 16

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 32 T 33S R 12W

FARM McCracken

NO. UNIT #1

LOC. NW, SW, SW


TOTAL DEPTH 4725'

COUNTY Barber Col, Kansas

COMM. January 23, 1957

COMP. February 7, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 258' W/225 sax.
5 1/2" @ 4722' W/100 sax.

ELEVATION 1495' DF

PRODUCTION Mississippian

FIGURES INDICATE BOTTOM OF FORMATIONS

100	Surface soil & sand	Elgin	3532'
258	Red bed	Heebner	3721
995	Red bed & shale	Douglas	3827
1400	Shale & shells	Lansing	3926
3060	Lime & shale	Mississippi	4594'
3290	Lime		
3770	Lime & shale		
4346	Lime		
4447	Cherty lime.		
4612	Lime		
4675	Chert & lime		
4708	Chert		
4725	Shale		
4725	T. D.		

PLUGGING
 FILE SEC. 32 T 33 R 12W
 BOOK PAGE 123 LINE 6

State of KANSAS

County of BARTON

ss:

I, Verne A. Morris of Garvey Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 McCracken Unit well

Subscribed and sworn to before me this 26th day of February 19 57

My Commission Expires: July 11, 1960

Verne A. Morris
 RECEIVED
 STATE CORPORATION COMMISSION
 SEP 23 1958
 NOTARY PUBLIC
 CONSERVATION DIVISION
 Wichita, Kansas