


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County, Sec. 35 Twp. 33S Rge. 12W (E) (W)

Location as "NE/CNWSW" or footage from lines NE NE NW
Lease Owner Atlantic-Richfield Co.
Lease Name Charles F. Bevans Well No. 1
Office Address Box 521, Tulsa, Okla. 74102
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 11-29-19 64
Application for plugging filed 7-27-19 76
Application for plugging approved 7-30-19 76
Plugging commenced 8-6-19 76
Plugging completed 8-12-19 76
Reason for abandonment of well or producing formation Not productive

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation Mississippi Depth to top Bottom Total Depth of Well 5151 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	363	None
				4 1/2	5144	3800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped sand from 5115 to 4590'
4 sacks cement from 4590 to 4550'
Ripped at 3800'
Wooden bridge at 230'
Rock from 230 to 220'
4 yards of ready mix to surface

RECEIVED
STATE CORPORATION COMMISSION

SEP 09 1976

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Clarke Corporation
Address Box 187, Medicine Lodge, Kansas 67104

STATE OF Kansas COUNTY OF Barton ss.
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 849 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7 th day of September, 19 76

My commission expires 11-30-79

[Signature]
Notary Public.

GABBERT-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

cc - ratton - Tulsa
cc - Wichita - Geological
cc - Kans. Geo. Soc.
cc - File
Verifax cc - State Corp. Comm.

SEVANS #1
NE NE NW SECTION 35-335-12W
BARBER COUNTY, KANSAS

COMMENCED: NOVEMBER 12, 1964
COMPLETED: NOVEMBER 30, 1964

OPERATOR - SINGLARI OIL & GAS COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	370	RED BED	RAN 11 JOINTS 5-5/8" CASING, SET @ 363' w/350 SRO CEMENT
370	440	RED BED	
440	760	RED ROCK	
760	1650	SHALE	
1650	3611	SHALE & LIME	
3611	3674	SHALE & SAND	
3674	3830	SHALE & LIME	
3830	3915	SHALE w/ LIME	
3915	4010	SHALE & LIME	
4010	4660	LIME	
4660	4824	LIME & SHERT	
4824	4980	LIME & SHALE	
4980	5005	SHALE	
5005	5025	VIOLA	
5025	5065	VIOLA LIME	
5065	5095	LIME	
5095	5149	SHALE & SAND	
5149	TD		RAN 150 JOINTS 4 1/2" CASING, SET @ 5145' w/250 SRO CEMENT

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN THE NE NE NW SECTION 35-335-12W, BARBER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 1ST DAY OF DECEMBER, 1964, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Vera A. McKenzie
VERA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1967

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1976

CORPORATION DIVISION
WICHITA, Kansas