

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 35 Twp. 33S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW NE  
Lease Owner Beardmore Drilling Company et al  
Lease Name Bevans 'B' Well No. 1  
Office Address 827 Beacon Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-25-65 19  
Application for plugging filed 1-24-65 19  
Application for plugging approved 1-24-65 19  
Plugging commenced 1-24-65 19  
Plugging completed 1-25-65 19  
Reason for abandonment of well or producing formation commercial quantities of oil not found  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4720 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	325'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug @ 300' w/ 1/2 sx. hulls, 2 sks. dry cem. 5 gal. water  
1/2 sk. hulls, 23 sks. cem. thru drill pipe  
Set plug @ 40' w/ hulls & 10 sks. cement.  
2 sks. cement in rathole.

RECEIVED  
STATE CORPORATION COMMISSION


JAN 29 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Walters Drilling Co.  
Address 510 Orpheum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Robert F. Walters (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Robert F. Walters  
510 Orpheum Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of January, 19 65  
Juanita M. Green  
Notary Public.



DRILLER'S LOG

COMPANY: BEARDMORE DRILLING COMPANY ET AL  
 827 BEACON BUILDING  
 WICHITA, KANSAS

WELL NAME: BEVANS 'B' #1  
 LOCATION: SW NW NE SEC. 35-33S-12W  
 BARBER COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.  
 510 ORPHEUM BUILDING  
 WICHITA, KANSAS

ROTARY DRILLING COMMENCED: JANUARY 15, 1965  
 ROTARY DRILLING COMPLETED: JANUARY 25, 1965

ELEVATION: 1559 KB  
 1556 DF  
 1554 GL

CASING RECORD: 8 5/8" set @ 325' w/ 225 sacks cement

LOG

0 - 325	Shale and Sand
325 - 1765	Shale
1765 - 1920	Shale and Lime Streaks
1920 - 2230	Lime and Shale
2230 - 2490	Lime
2490 - 2745	Shale and Lime
2745 - 3135	Shale
3135 - 3348	Shale and Lime
3348 - 3485	Shale, Lime and Shells
3485 - 3651	Shale and Lime
3651 - 3710	Sand
3710 - 3840	Shale and Lime Streaks
3840 - 4000	Shale and Lime
4000 - 4105	Lime and Shale
4105 - 4165	Lime
4165 - 4360	Lime and Shale
4360 - 4485	Lime
4485 - 4530	Lime and Shale
4530 - 4615	Lime
4615 - 4670	Lime and Shale
4670 - 4720	Lime
<u>4720</u>	<u>Rotary Total Depth - D &amp; A</u>

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JAN 29 1965  
 CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY

*Robert F. Walters*  
 Robert F. Walters, Partner

STATE OF KANSAS )  
 COUNTY OF SEDGWICK) ss:

BE IT REMEMBERED that, on this 27th day of January, 1965, before me, the undersigned, a Notary Public duly commissioned in and for the State and County aforesaid, came Robert F. Walters, known to me to be the same person who executed the foregoing instrument as Partner and in behalf of the Walters Drilling Co. and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My Commission Expires:  
 October 4, 1967

*Juanita M. Green*  
 Juanita M. Green, Notary Public

