

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

BARBER

County. Sec. 25 Twp. 33 Rge. 12 (X) W (W)

Location as "NE/CNW&SW" or footage from lines NE NW SW

Lease Owner PETROLEUM INC.

Lease Name LONG "D" Well No. 1

Office Address Route 2, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 8 19 57

Application for plugging filed January 8 19 57

Application for plugging approved January 8 19 57

Plugging commenced January 8 19 57

Plugging completed January 8 19 57

Reason for abandonment of well or producing formation No Producing Zones

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives, Box 8, Pratt, Kansas

Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 4622' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	238'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up with heavy mud to 225', pushed down 1/3 sack hulls to 225' followed by wooden plug. Placed 20 sacks cement through drill pipe on to plug. Mud up to 35' and place 1/3 sack hulls at 35' followed by wooden plug and 10 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Co.
Address Route 2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (owner/operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 57

My commission expires July 11, 1960

STATE CORPORATION COMMISSION Notary Public.

PLUGGING
FILE SEC 25 T 33 R 12 W
BOOK PAGE 132 LINE 44

JAN 11 1957
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY: PETROLEUM, INCORPORATED

SEC. 25 T. 33S R. 12W

FARM: LONG 'D' NO. 1


LOC: NE, NW, SW

TOTAL DEPTH: 4622'

COUNTY: Barber Co., Kansas

COMM: December 24, 1956 COMP: January 8, 1957

CONTRACTOR: GARVEY DRILLING COMPANY



CASING: 8 5/8" @ 238' W/200 sax.

ELEVATION: 1462' DF

PRODUCTION: D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

75	Red rock	Elgin	3458
238	Red bed & shells	Heebner	3670
885	Red bed & shale	Douglas	3754
1550	Shale & shells	Lansing	3850
2095	Lime & shale	Base K.C.	4355
2345	Lime	Mississippi	4522
2950	Lime & shale		
3180	Lime		
3720	Lime & shale		
3805	Lime & shale & sand		
3826	Sand		
3928	Sand, shale & lime		
4423	Lime		
4490	Lime & shale		
4535	Shale & sand		
4550	Chert		
4622	Cherty lime.		
4622	T. D.		

State of KANSAS
 County of BARTON
 I, Verne A. Morris

PLUGGING
 FILE SEC. 25 T. 33 R. 12W
 BOOK PAGE 122 LINE 420

RECEIVED
 CORPORATION COMMISSION
 JAN 11 1957
 CONSERVATION DIVISION
 Wichita, Kansas
 Garvey Drilling Co.

upon oath, state that the above and foregoing is a true and correct copy of the log of the #1 Long 'D' well

Verne A. Morris

Subscribed and sworn to before me this 9th day of January 1957

My Commission Expires: July 11, 1960

Jed T. Brown
 NOTARY PUBLIC