

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barber

County. Sec. 25 Twp. 33 Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines C N 1/2 NW 1/4

Lease Owner Bachus Oil Company

Lease Name McKanna Well No. # 1

Office Address 721 E. Central, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) GasWell

Date well completed 8-1 1956

Application for plugging filed yes 19

Application for plugging approved yes 19


Plugging commenced 3-8-60 19

Plugging completed 3-28-60 19

Reason for abandonment of well or producing formation Well no longer capable of producing gas in commercial quantities

If a producing well is abandoned, date of last production 9-24 1959

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Missippian Depth to top 4538 Bottom 4780 Total Depth of Well 5013 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4739'	4,200'
				8-5/8"	320'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 3-8-60. Plugging completed 3-28-60. Measured into total depth 4595'. Plugged off bottom: Sanded back up hole to 4560'. Dumped 4 sacks of cement. Loaded hole with water. Worked and shot pipe. Shot 5 1/2" casing at 4200'. Pulled and laid down pipe. Plugged well: Mudded hole up to 300'. Set 10' rock bridge. Dumped 20 sacks of cement. Mudded hole up to 40'. Set 10' rock bridge. Capped the well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company

Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of March, 1960

Kayann Jenkins
Notary Public.

My commission expires December 8th, 1963



ROTARY DRILLING LOG

OPERATOR: Bachus Oil Co.
 McKanna #1
 C N/2 NW/4 Sec. 25-33-12W,
 Barber County, Kansas.

CONTRACTOR: Prime Drilling Company
 COMM: 6/1/56
 COMP: 6/23/56

Remarks: Set 8-5/8" surface casing
 at 320' cemented with 250 sacks common
 cement, 2% C.C.

Formations:

Surface Clay	40'
Red Bed & Shells	321'
Red Bed & Shale	825'
Shale & Shell	1325'
Anhydrite & Shale	1360'
Shale Lime	1685'
Lime	1980'
Lime & Shale	3210'
Lime	3380'
Shale & Lime	3750'
Lime	3800'
Shale Lime Sand	3863'
Lime & Shale	3880'
Lime	4400'
Lime & Shale	4420'
Lime	4555'
Cherty Lime	4600'
Lime & Shale	4685'
Lime Shale & Chert	4715'
Lime & Shale	4805'
Lime	4845'
Lime & Shale	4917'
Lime Shale & Chert	4945'
Shale & Chert	4962'
Shale & Lime	4986'
Lime Shale & Chert	5000'
Lime & Sand	5008'
Sand	5013'
Rotary Total Depth	5013'

RECEIVED
 STATE CORPORATION COMMISSION

MAR 31 1960

CONSERVATION DIVISION
 Wichita, Kansas

Set 5-1/2" casing at 4739' cemented with
 150 sacks common cement.

We certify the above log is true and
 correct to the best of our knowledge
 and belief.

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol