

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-077-21,328-00-00

LEASE NAME Bartholow

WELL NUMBER 1

SPOT LOCATION C-s/2 N/2 of SW

SEC. 4 TWP. 33 RGE. 12 (E) or (W)

COUNTY Barber

Date Well Completed 1-4-82

Plugging Commenced 12-13-1985

Plugging Completed 12-17-1985

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Reach Group

ADDRESS 229 E. Williams, Suite 500, Wichita, KS. 67202

PHONE # (316) 262-1515 OPERATORS LICENSE NO. 8572

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Miss. Osage Depth to top 4468 bottom 4508 T.D. 4932'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	404'	0'
Production				4 1/2"		2633'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 2 sks. hulls & 20 sks. cement to 4220' & pressured to 700 lbs., displaced w/mud to 460' pumped 50 sks. cement 460' to 310' Displaced w/mud to 40', put bridge & 10 sks. cement 40' to 0', cut off 8 5/8", 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497  
Address Box F, Sublette, Ks. 67877

STATE OF Kansas COUNTY OF Haskell, ss.

I, Edgar J. Eves

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 2nd day of Jan., 19 86

My Commission expires: 12-6-88

Londra L. Eves  
Notary Public

