


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 6 Twp. 33 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner Aylward Drilling Company
Lease Name Alexander Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6-11-62 19
Plugging completed 6-13-62 19
Reason for abandonment of well or producing formation Depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp
Producing formation Depth to top Bottom Total Depth of Well 3890 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	224'	None
				5-1/2"	3869'	3114'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3890', sanded to 3850' and dumped 5 sacks of cement @ 3850' with dump bailer. Pulled 5 1/2" casing. Mudded hole to 200', set rock bridge to 190' and ran 20 sacks of cement. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1962

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KK KANSAS
(If additional description is necessary, use BACK of this sheet)

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1962

My commission expires May 20, 1964

Milton J. Volin
Notary Public.



WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company: ORVILLE PARKER OIL CO.
Farm: Alexander No. 2

SEC. 6 T. 33 R. 12W
C SE NW

Total Depth. 3890'
Comm. 4-25-52 Comp. 5-11-52
Shot or Treated.
Contractor.
Issued. 8-14-54

County Barber
KANSAS



CASING:
8 5/8" 223.97' cem w/150 sx
5 1/2" 3869' cem w/100 sx

Elevation. 1693'

Production. 129,850,000 gas & no
wtr.

Figures indicate Bottom of Formations.

no log	225
red bed	600
shale & shells	870
shale & shells	1315
shale & shells	1500
shale & lime	1600
shale & lime	1800
lime & shells	1920
lime	2260
lime & shale	2350
shale & lime	2368
lime & shale	2375
lime	2445
lime & shale	2600
lime broken	2680
lime	2780
shale & lime	2835
lime & shale	2925
lime & shale	3105
lime	3175
sand	3185
lime & shale	3365
lime	3400
shale & lime	3580
lime & shale	3795
shale & lime	3875
sand	3885
sand	3890
Total Depth	
Tops: Scout	
Tonganoxie	3873

RECEIVED
STATE CORPORATION COMMISSION

AUG 9 1 1962

CONSERVATION DIVISION
Wichita, Kansas