


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

HARPER County, Sec. 4 Twp. 31s Rge. 6 (X) (W)
Location as "NE/CNW/SW" or footage from lines App. C NW SW
Lease Owner PETROLEUM, INC.,
Lease Name THOMAS 'F' Well No. 1
Office Address R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed NOVEMBER 21 19 66
Application for plugging filed NOVEMBER 21 19 66
Application for plugging approved NOVEMBER 21 19 66
Plugging commenced NOVEMBER 21 19 66
Plugging completed NOVEMBER 21 19 66
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4394 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	202'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

HEAVY MUD TO 200', FOLLOWED BY WOODEN PLUG, PLACED 15 SACKS CEMENT, 1/2 SACK HULLS ON TOP OF PLUG. HEAVY MUD TO 40', FOLLOWED BY WOODEN PLUG, PLACED 10 SACKS CEMENT AND 1/2 SACK HULLS ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1966
12-8-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRLG. CO.
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (XXXXXXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*
R.R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 7 day of DECEMBER, 19 66

My commission expires MAY 28, 1969

Richard H. Duncanson
Notary Public.

K-077-3011-0000

WELL LOG

COMPANY Petroleum, Incorporated

SEC. 4 T. 31S R. 6W

FARM Thomas

NO. F-1

LDC. App C-NW-SW


TOTAL DEPTH 4394'

COUNTY Harper

COMM. 11-10-66

COMP. 11-21-66

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 202' w/200 SX

ELEVATION 1560' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 42' Sand
- 205' Red Bed
- 550' Shale
- 1150' Shale and Shells
- 1160' Anhydrite
- 1180' Shale
- 1280' Lime and Shale
- 1580' Shale with Lime
- 1800' Lime and Shale
- 2386' Shale and Lime
- 2775' Lime with Shale
- 2955' Shale with Lime
- 3156' Lime with Shale
- 3255' Shale and Lime
- 3350' Lime
- 3605' Lime and Shale
- 4265' Lime
- 4335' Shale and Lime
- 4361' Shale with Lime and Chert
- 4365' Lime
- 4384' Cherty Lime
- 4394' Lime with Chert
- 4394' RTD

RECEIVED
 STATE GEOLOGICAL COMMISSION
 DEC 8 1966
 12-8-66
 CORRELATION DIVISION
 STATE OF KANSAS

State of Kansas }
 County of Barton } ES

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Thomas No. F-1 well.

Sam N. Stephens

Subscribed and sworn to before me this 6th day of December 19 66

My Commission Expires: November 5, 1969

Richard D. Boye
 NOTARY PUBLIC