

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1963

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Co.

Complete Address: Box 30, Lyons, Kansas

Lease Name: A. Smith Well No. # 1

Location: C SE SE SW Sec. 13 Twp. 31 Rge. 13 (E) (W) W

County Barber Total Depth 4670 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Deacon was instructed to plug the well as follows:

260' of 13 3/8" surface pipe, cement circulated with 275
sacks. 4303' of 5 1/2" long string, cemented with 350 sacks.

Plugged back to 4274', Top perforation 3569'. Sand to
3550', cement with 6 sacks. Fill hole with mud to 250',

10' rock bridge, cement with 35 sacks. Fill hole with mud
to 40', 10' rock bridge, cement with 20 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent