

15-007-20055-00-00

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed February 27, 1968.

Dear Sir:

Mr. Calvin Roberts of Leben Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Tilco

Complete Address: 815 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: Smith Well No. # 1

Location: C NE SW Sec. 27 Twp. 31 Rge. 13 (E)(W) W

County Barber Total Depth 3778' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

320' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks, to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent