



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

**RECEIVED**  
 NOV 20 1967  
 CONSERVATION DIVISION  
 Wichita, Kansas

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Nov 14, 1967.

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Carlson & Faulconer

Complete Address: 336 Union Center Wichita Kansas.

Lease Name: Brooks Well No. #1

Location: NW-NW-SE Sec. 32 Twp. 31 Rge. 13W (E) (W) W

County Barber Total Depth 4840 Oil Well     

Gas Well X Input Well      SWD Well      D & A      Lost Hole     

Mr. Bailey was instructed to plug the well as follows:

210' of 13 3/8" surface pipe circulated with cement. 4449'  
of 5 1/2" pipe. Top perforation at 3739', Plug set at 3700',  
and 5 sacks cement. Mud to 210', 10' rock bridge & 35 sacks  
cement. Mud to 40', 10' rock bridge & 15 sacks cement to  
base of cellar. 3000' of 5 1/2" pipe pulled.

Very truly yours,

*H. L. ...*  
 Conservation Division Agent