



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1962
9-13-62
CONSERVATION DIVISION
Wichita

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date Sept, 11 1962, 1962, authorized
the following plugging operation:

Operator's full Name: E. K. Cary Contractor.

Complete Address: 1050 Petroleum Club Bldg. Denver, Colo.

Lease Name: Peace Treaty Well No. #7

Location: NE NE SE Sec. 7 Twp. 32 Rge. 11 (E) (W) X

County Barber Total Depth 4721'

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: (washdown)

Operator was instructed to plug well as follows:

283' of 8 5/8" surface pipe circulated with cement. Hole
filled to 250' with heavy drilling mud, 1/2 sack hulls,
1st cementing plug, 25 sacks cement through drill pipe
by Globe Cementing Co. Hole filled to 35' with heavy drilling
mud, 1/2 sack hulls, 2nd cementing plug and 10 sacks cement
to base of cellar. Rat hole bridged and 25 sacks cement.

Herman Justus
Conservation Division Agent