

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20954-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 6-23S-16W
341 feet from S Section Line, 4863 feet from E Section Line
Lease Name: FRICK A Well #: 2
County: PAWNEE Total Vertical Depth: 4250 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4249	1374	WITH 150 SX CMT
SURF	8.625	337		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/22/2013 10:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4170' WITH 2 SX CMT. PLUG AT 1020' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/22/2013 12:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

COULDN'T WORK ANY TOOLS PAST 2180. RAN TBNG TO 2180' & SPOTTED 30 SX CMT WITH 100# HULLS MIXED IN. HAD GOOD CIRCULATION. TOC ON BOTTOM PLUG 1430'. 1ST PLUG AT 1032' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 356' WITH 50 SX CMT. 3RD PLUG AT 59' WITH 60 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4158	4188		
4120	4128		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

SEP - 6 2013

KCC DODGE CITY

Signed

[Handwritten Signature]
11/08/13

(TECHNICIAN)

KCC WICHITA

SEP 18 2013

RECEIVED

Form CP-2/3

[Handwritten Signature]