

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20152-00-00
Spot: NENWSE Sec/Twnshp/Rge: 24-15S-13W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: PIESTER Well #: 1
County: RUSSELL Total Vertical Depth: 3333 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3324		100 SX
SURF	8.625	242		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2013 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG HUTCHINSON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Perforations: 1500', 850', 240'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2013 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2900' and pumped 50 sx cement followed by 100 sx cement w/400 # hulls.
Pulled tubing to 1500' and pumped 75 sx cement w/100 # hulls.
Pulled tubing to 825' and pumped 65 sx cement w/300 # hulls.
Cement circulated out the back side.
POOH. Hooked to casing and pumped 60 sx cement.
Cement circulated out the braden head. Closed valve on braden head and pressured casing to 250 psi. Shut in.

GPS: 38.73217 -098.71359

Perfs:

Top	Bot	Thru	Comments
3116	3119		
3107	3112		
3094	3098		
3075	3079		

KCC WICHITA

Remarks: QUALITY CEMENTING TICKET # 5892

SEP 19 2013
RECEIVED

Plugged through: TBG

District: 04

Signed Ray Dinkel (TECHNICIAN)

CM

SEP 12 2013