

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20830-00-00
Spot: NW Sec/Twnshp/Rge: 6-10S-24W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: RIEDEL Well #: 2
County: GRAHAM Total Vertical Depth: 4031 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3793		
PROD	5.5	4029		275 SX
SURF	8.625	204		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2013 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls
CIBP at 3793', Perforations at 3764' - 3768'.
Shot perforations at 2120' and 1250'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2013 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3712' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 2227' and pumped 100 sx cement w/225 # hulls. Pulled tubing to 1260' and pumped 130 sx cement. Cement circulated. Topped off casing with 65 sx cement. Ran out of cement. WOC till next day. Redi Mix truck topped off casing with 3 1/4 yards cement. Casing full. Tied on to back side and squeezed with 5 sx cement. Shut in pressure 200 psi.

GPS: 39.21527 -100.04734

Perfs:

Top	Bot	Thru	Comments
3941	3946		
3917	3922		
3821	3824		
3764	3768		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: SWIFT CEMENT TICKET # 25205 S&R REDI MIX TICKET # 868


OCT 15 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed


10/08/13 (TECHNICIAN)

CM

OCT 03 2013