

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01990-00-00
Spot: NESESE Sec/Twnshp/Rge: 1-10S-20W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: SUTOR A Well #: 3
County: ROOKS Total Vertical Depth: 3765 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3764		150 SX
SURF	8.625	151		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2013 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/800 # hulls.
08-30-13: Ordered 500 sx 60/40 pozmix 4% gel cement w/1000 # hulls
Squeezed from 771' - 800' w/60 sx cement, 1045' - 1075' w/80 sx cement, 1250' - 1254' w/400 sx cement, 1500' - 1560' w/80 sx cement, 1856' - 1887' and 1947' - 1978' w/250 sx cement.
Tried to mill casing and could not get past 1953'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2013 9:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1946' and pumped 360 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Pulled tubing to 1005' and pumped 140 sx cement w/200 # hulls. Pulled all tubing and let well set overnight.
08/30/13: Ran tubing in hole and tagged cement at 810'. Pulled tubing up to 780' and pumped 130 sx cement w/200 # hulls.
Pulled tubing and topped off 5 1/2" casing w/5 sx cement.
Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Shut in pressure 200 psi.

Perfs:

Top	Bot	Thru	Comments
3764	3766		

Remarks: QUALITY OILWELL CEMENTING TICKET # 7299 AND 7300

Plugged through: TBG

District: 04

Signed

Pat Bedore
11/08/13 (TECHNICIAN)

CM

SEP 06 2013

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

OCT 02 2013
CONSERVATION DIVISION
WICHITA, KS