

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02406-00-00
Spot: SWNESW Sec/Twnshp/Rge: 25-14S-13W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: WEIMEISTER A Well #: 8
County: RUSSELL Total Vertical Depth: 3124 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2871		
CIBP		2954		
PROD	5.5	3107		100 SX
SURF	8.625	608		325 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2013 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement, 75 sx gel and 300 # hulls. Perforations at 1250' and 300'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2013 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2770' and pumped 7 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 1300' and pumped 150 sx cement w/100 # hulls. Cement circulated out backside. POOH. Hooked to casing and pumped 55 sx cement. Cement circulated out braden head. Shut in and pressured casing to 500 psi. Shut in.

GPS: 38.80290 -098.71946

Perfs:

Top	Bot	Thru	Comments
3107	3124		
2854	2865		
2835	2841		
2815	2824		
2763	2769		
2166	2182		

Remarks: QUALITY CEMENTING TICKET # 7545

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel
10/08/13

(TECHNICIAN)

CM

KCC WICHITA

OCT 29 2013

NOV 04 2013

Form CP-2/3

RECEIVED