

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00699-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 28-16S-10W
990 feet from S Section Line, 1980 feet from E Section Line
Lease Name: LOULA A&B Well #: B-2
County: ELLSWORTH Total Vertical Depth: 3320 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3309		175 SX
SURF	8.625	345		110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2013 3:00 PM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: DAN WEINHOLD Company: DAN'S PACKER SERVICE Phone: (785) 483-1307

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/01/2013 4:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ATTEMPT TO PULL TUBING - COULD NOT. PAST SQUEEZE'S HAVE BEEN PERFORMED ON WELL. GLM CO. HAS PRODUCED THIS WELL UNDER A PACKER FOR SEVERAL YEARS. BACKED TUBING OFF @ AROUND 2700'. SET STANDING VALVE ON TO TUBING TO GET WASH OVER PIPE, OVER. WENT BACK IN WITH WASH-OVER PIPE AND TUBING -- COULDN'T GET PAST 430'. RIGGED UP MUD PUMP AND POWER SWIVEL -- DRILLING THRU LOTS OF RED SALE --AFTER SEVERAL DAYS WORK, FINALLY GOT TO ABOUT 620'. RIGGED UP ANOTHER MUD PUMP TO CIRCULATE MUD TO KEEP CIRCULATION. EACH DAY, HAD TO RE-DRILL FROM 430' TO 580' AND FINALLY 620'. PUMPED 60 SX'S COMMON CEMENT -- CIRCULATED TO SURFACE. PULL TUBING OUT AND TOP OFF. CAME BACK ON 10-2-2013 AND TOPPED OFF WITH SLURRY MIX. CEMENT WAS PRESENT IN SURFACE CASING ON BACKSIDE OF PRODUCTION CASING.

Perfs:

Top	Bot	Thru	Comments
3052	3055	CSG	
3010	3013	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: QUALITY CEMENT TICKET #7784. ELLSWORTH REDI-MIX TICKET #43584.

Plugged through: TBG

OCT 16 2013
CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Virgil Clothier
10/08/13 (TECHNICIAN)

Form