

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25640-00-00
Spot: N2SESESW Sec/Twnshp/Rge: 5-17S-24W
600 feet from S Section Line, 2310 feet from W Section Line
Lease Name: SOMY Well #: 1-5
County: NESS Total Vertical Depth: 4570 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	214		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/30/2013 6:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: MARK BIGGE Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1875' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 08/30/2013 8:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

1ST PLUG AT 1875' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: DP

KCC WICHITA
SEP 12 2013
RECEIVED

District: 01

Signed Ken Jehlik
SEP 13 (TECHNICIAN)

RECEIVED
SEP - 6 2013
KCC DODGE CITY

AWY