

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23243-00-00
Spot: N2NESW Sec/Twnshp/Rge: 15-25S-15W
2253 feet from S Section Line, 3196 feet from E Section Line
Lease Name: HART A Well #: 4
County: STAFFORD Total Vertical Depth: 4278 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2600		WITH 2 SX CMT
CIBP		2760		
CIBP		3250		
CIBP		4000		
DVT		3350		WITH 200 SX CMT
PROD	4.5	4276		WITH 325 SX CMT
SURF	8.625	343		WITH 250 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/19/2013 11:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 2600' WITH 2 SX CMT. PLUG AT 930' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2013 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 2600' WITH 2 SX CMT. 1ST PLUG AT 941' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 382' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4184	4199		SPF
3923	3925		SPF
3815	3820		SPF
3204	3207		SPF
3137	3147		SPF
2712	2717		SPF
2645	2649		SPF

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 10 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED

District: 01

SEP - 6 2013

Signed

Michael Maier
1087 B (TECHNICIAN)

KCC DODGE CITY

10/10/13