

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20976-00-00
Spot: W2NWSW Sec/Twnshp/Rge: 25-17S-10W
1986 feet from S Section Line, 4959 feet from E Section Line
Lease Name: HOFFMAN Well #: 1
County: ELLSWORTH Total Vertical Depth: 3325 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3216		
PROD	4.5	3324	1643	125 SX
SURF	8.625	370		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2013 1:00 PM
Plug Co. License No.: 34032 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE Phone: (620) 655-4494

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 09/11/2013 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING OUT. CHECK BOTTOM, SET CIBP @ 3216' AND CAP WITH 4 SXS CEMENT. CUT CASING OFF AT 1643' AND PULL OUT OF HOLE. RUN TUBING TO 1250' AND PUMP 15 SX'S GEL FOLLOWED BY 35 SX CEMENT, PULL TUBING TO 950' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 420' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3266	3270	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 08 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: GEMINI WIRELINE TICKET #0569. ALLIED CEMENT TICKET #061772. DENIED TA STATUS - DUE TO NO VALID OIL & GAS LEASE, & HGFLD.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
10/8/13 (TECHNICIAN)