

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-00665-00-00  
Spot: SWNWNWSE Sec/Twnshp/Rge: 18-16S-10W  
2296 feet from S Section Line, 2336 feet from E Section Line  
Lease Name: KOZISEK Well #: 1  
County: ELLSWORTH Total Vertical Depth: 3407 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3240		60 SX
SURF	8.625	336		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/24/2013 12:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.

Proposal Rcvd. from: JORDAN DISKIN Company: \_\_\_\_\_ Phone: (316) 303-4691

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/27/2013 3:00 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

SET PLUG @ 2950', 35 SKS CLASS A 3% GEL, TAGGED @ 2478', PERF @ 1400' RAN TUBING TO 1418' PUMPED 15 SKS GEL, THEN 35 SKS OF 60/40 4%, PERF @ 1098' RAN TO 1120' SET 35 SKS OF 60/40 4%, PULLED UP TO 390' PERF RAN TO 416' TO 65 SKS TO CIRCULATE TO SURFACE. CASING STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
3183	3075		

Remarks: TICKET #061887 ALLIED GREAT BEND

Plugged through: TBG

KCC WICHITA

OCT 29 2013

RECEIVED

District: 02

Signed

[Signature]  
11/08/13 (TECHNICIAN)