

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-35031-00-00
Spot: NWNWSWSE Sec/Twnshp/Rge: 18-16S-10W
1294 feet from S Section Line, 2324 feet from E Section Line
Lease Name: KOZISEK Well #: 2
County: ELLSWORTH Total Vertical Depth: 3370 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3360		110 SX
SURF	8.625	340		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2013 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BERRY Company: _____ Phone: (316) 303-4691

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 09/26/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

COULD NOT GET WIRELINE DOWN CASING. RAN IN WITH TUBING TO 3330'
SPOTTED 50 SX OF CEMENT ON 9/24/13. 9/25/13 TAGGED TOP OF CEMENT @ 2906'.
CUT CASING PIPE OFF @ 1476' PULLED CASING. RAN TUBING INTO 1408'
SPOTTED 35 SX OF CEMENT, PULLED TUBING TO 1088' SPOTTED 35 SX OF
CEMENT, PULLED TUBING TO 384' CIRCULATED TO SURFACE WITH 115 SX OF
CEMENT. 9/26/13 CEMENT FELL BACK 200', NO FLUID IN WELL BORE SO FILL TO
SURFACE WITH 55 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3360	3186		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 04 2013

Remarks: ALLIED CEMENT CO. PLUG DUE TO DENIED TA.

Plugged through: TBG

District: 02

Signed

B. J. Hope
11/08/13

(TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KS