

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21365-00-01
Spot: NWSENWSW Sec/Twnshp/Rge: 11-32S-33W
1958 feet from S Section Line, 4579 feet from E Section Line
Lease Name: PRINTZ TRUST Well #: 1-11
County: SEWARD Total Vertical Depth: 2820 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2604		WITH 2 SX CMT
CIBP		2704		
PROD	4.5	2818	0	WITH 425 SX CMT
SURF	8.625	1700		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/16/2013 8:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 2604' WITH 2 SX CMT. PLUG AT 1740' WITH 20 SX GEL & 50 SX CMT. PLUG AT 540' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2013 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 2604' WITH 2 SX CMT. RTIH TO 1750' & PUMPED 125 SX CMT. CMT CIRCULATED. CHECK BACKSIDE WITH 10 SX CMT AT 600#.

Perfs:

Top	Bot	Thru	Comments
2708	2718		
2690	2700		
2654	2667		
2642	2646		
2632	2638		
2615	2620		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 01 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

[Handwritten Signature]
21/08/13 (TECHNICIAN)

RECEIVED

SEP 19 2013

KCC DODGE CITY

[Handwritten Mark]