

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-21748-00-00  
Spot: SWNESESW Sec/Twnshp/Rge: 9-26S-14W  
942 feet from S Section Line, 3003 feet from E Section Line  
Lease Name: HUTCHINS B Well #: 1  
County: PRATT Total Vertical Depth: 4575 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PLG	4.5	4270		
PROD	4.5	4574	1998	WITH 200 SX CMT
SURF	8.625	416		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/12/2013 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3915' & 4 SX CMT. PLUG AT 960' WITH 15SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/12/2013 12:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

\*\*PULLED PIPE TO 1620'. HIT SMALL GAS POCKET UNLOADING HOLE UP CASING.\*\* SANDED TO 3907' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 957' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 429' WITH 50 SX CMT. 3RD PLUG AT 33' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4276	4280		
3985	3998		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

RECEIVED  
SEP 16 2013  
KCC DODGE CITY

Signed Richard M. Lacey  
9/15/13 (TECHNICIAN)

KCC WICHITA Form CP-2/3

SEP 18 2013

RECEIVED

RAW