

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23724-00-00
Spot: SWNWSESE Sec/Twnshp/Rge: 25-24S-12W
822 feet from S Section Line, 1111 feet from E Section Line
Lease Name: KEIM Well #: 1-25
County: STAFFORD Total Vertical Depth: 4150 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4126	2150	WITH 125 SX CMT
SURF	8.625	267		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/06/2013 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: PUMP 200-300# HULLS WITH 50 SX CMT. PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL
Date/Time Plugging Completed: 09/06/2013 8:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 70 SX CMT WITH 200# HULLS MIXED IN. DISPLACED TO 3420'. 1ST PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 41' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3948	3954		
3924	3932		
3586	3954		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
9/15/13 (TECHNICIAN)

RECEIVED
SEP 13 2013
KCC DODGE CITY

KCC WICHITA
Form CP-2/3
SEP 18 2013
RECEIVED