

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23738-00-00
Spot: NESEWNNE Sec/Twnshp/Rge: 27-24S-12W
744 feet from N Section Line, 1554 feet from E Section Line
Lease Name: MOORE Well #: 1-27
County: STAFFORD Total Vertical Depth: 4150 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4145	2006	WITH 160 SX CMT
SURF	8.625	280		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/09/2013 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: PUMP 90 SX CMT DISPLACED TO 3200'. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL
Date/Time Plugging Completed: 09/09/2013 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 100 SX CMT WITH 3% CC DOWN THE 5 1/2" CASING. LET CMT SET. TAGGED CMT AT 3154'. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4076	4079		
3364	4079		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Eric MacLaren (TECHNICIAN)
9/15/13

RECEIVED
SEP 13 2013
KCC DODGE CITY

KCC WICHITA Form CP-2/3

SEP 18 2013

RECEIVED