

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-19511-00-01  
Spot: NESWSWSW Sec/Twnshp/Rge: 33-34S-12E  
649 feet from S Section Line, 4730 feet from E Section Line  
Lease Name: WOLFE Well #: 10  
County: CHAUTAUQUA Total Vertical Depth: 1098 feet

Operator License No.: 32856  
Op Name: RUTLEDGE, JACK DBA J R OIL  
Address: PO BOX 273  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	2.5	44		
SURF		45		

Well Type: EOR UIC Docket No: E24696.1 Date/Time to Plug: 07/16/2013 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' plug at TD, 350' to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/16/2013 12:00 PM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Operator had tried to repair the casing by squeezing cement into hole in casing. Ran 1" to 1000' and gelled over the perfs. Pulled up to 950' spotted 2 sks cement. Pulled 1" out Pumped Flag, found hole at 32'. Squeeze hole with 60 sks cement. Drilled out cement to 100'. Tested squeeze repair and it wouldn't pass. Drill down to 350' and was still drilling cement. Ran 1" to 350' and circulated cement to surface with 10 sks. A total of 72 sacks of cement were used to plug this well including the cement used to squeeze the hole in casing.

**Perfs:**

RECEIVED

OCT 08 2013

KCC Chanute Dist. #3

DS

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT

Plugged through: TBG

District: 03

Signed

*[Signature]*  
✓ 11/18/13

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 10 2013

CONSERVATION DIVISION  
WICHITA, KS